Registered No. M.—1175.

The Mysore Gazette.

Vol. 55.] PUBLISHED BY AUTHORITY. [No. 49

BANGALORE, THURSDAY, DECEMBER 9, 1920.

PART VI.

PUBLIC ADVERTISEMENTS.

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Dated 30th November 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 4 P.M., on Monday the 13th December 1920, for constructing an Hostel for the High School at Channapatna. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1922.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompained by a deposit of Rs. 500 (Five hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an Hostel for the High School at Channapatna" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Description	Per	Quantity
1	Earthwork excavating foundation	C. yd.	290
2	Chunam concrete	C. ft.	2,655
3	Burnt stone in mud (in foundation)	C. ft.	3,267
	Do do basement with chunam pointing ...	C. ft.	2,563
4	Burnt brick in mud (superstructure including bond stone) ...	C. ft.	12,040
5	Honnewood doors, ¾ panelled and ¼ glazed with iron works, etc., as per design	S. ft.	517
6	Honnewood battened doors with iron clamps, hinges, etc. ...	S. ft.	279
7	Honnewood windows, ½ panelled and glazed shutters with iron bars, complete	S. ft.	599
8	Honnewood battened windows with iron bars, etc., complete	S. ft.	244
9	Honnewood glazed ventilators with manilla ropes, etc., complete	S. ft.	419
10	Honnewood glazed ventilators with longitudinal iron bars, etc., complete.	S. ft.	138
11	Burnt stone slabs, 4" to 6" thick, dressed	S. ft.	1,103
12	Do 3" thick, dressed	S. ft.	36
13	Honnewood work, wrought and put up including wood oiling, two coats	C. ft.	306.44
14	Chunam plastering	Sqr.	234.00
15	White and colourwashing (two coats)	Sqr.	226.00
16	Stone brackets, dressing, etc., complete as per design ...	each	6
17	Roofing with 1st class Mangalore tiles over teak reepers, etc. ...	Sqr.	8,042
18	Ridge tiles set in mortar	R. ft.	307
19	Zinc sheets to valley	S. ft.	156
20	Chunam border over roof as per design including plastering, etc.	R. ft.	90
21	Earthwork filling in basement including and tamping ...	C. yd.	73
22	Flooring with Cuddappah slabs over 3" concrete bed, cement pointing	Sqr.	2,167
23	Flooring with 1st class square Mangalore tiles over 3" concrete bed including cement pointing, etc., complete ...	Sqr.	2,088
24	Silicate painting, etc., two coats	Sqr.	32.74
25	Honnewood eave board, plain, 6" wide including painting ...	R. ft.	608
26	Cornice work	R. ft.	56
27	Flooring with 6" stone slabs over concrete bed including chunam pointing, etc., complete	R. ft.	147
28	Coping with burnt brick in mortar and chunam plastering over compound wall in court-yard	R. ft.	128
29	U.-shaped drain with cement plastering	R. ft.	462
30	Wooden square finials as per design including, etc., complete ...	each	2
31	Stone in mortar	C. ft.	273
32	Whitewashing and tarring up to 3" high inside as per plastering	S. qr.	8.00
33	V.-shaped cement drain, 6" deep to bed of water ...	R. ft.	32
34	Gravel flooring, 6" thick	C. yd.	2
35	Size stones for seats of chullas with cement pointing, 1½' × 1' × 1'	No.	18
36	Tarring to wood work	L.S.R.	

T. S. RAGHAVACHAR,
Executive Engineer.

MISCELLANEOUS.

DEPARTMENT OF INDUSTRIES AND COMMERCE.

Dated 5th November 1920.

Notice is hereby given that separate sealed tenders for each group of articles noted below will be received at the Office of the Director of Industries and Commerce up to 10th January 1921. An approximate estimate of quantities is given below. These quantities are not guaranteed.

2. The articles will be required in equal quantities during the six months commencing from 1st January 1921, and the rates for supplies may either be uniform for all six months or different for each month.